

SUBSURFACE IRRIGATION

SYMBOL	MANUF.	MODEL NO. / DESCRIPTION	DETAIL
[Symbol]	HUNTER	IC2-101-40-LF DRIP CONTROL ZONE KIT. 1" ICV GLOBE VALVE WITH 1" HY100 FILTER SYSTEM PRESSURE REGULATION. AOPSL. FLOW RANGE: 5 GPM TO 15 GPM. 150 MESH STAINLESS STEEL SCREEN.	SEE 11L204
[Symbol]	HUNTER	DRP LINE 0.4 GPM @ 12" O.C.	

IRRIGATION UTILITIES

SYMBOL	MANUF.	MODEL NO. / DESCRIPTION	DETAIL
[Symbol]		1" DEDICATED LANDSCAPE METER, SEE CIVIL ENGINEER DWGS.	
[Symbol]	WYATT	BASKET STRAINER	
[Symbol]	BUCKNER-SUPERIOR	3000 1-1/4" NORMALLY CLOSED BRASS MASTER VALVE THAT PROVIDES DIRTY WATER PROTECTION AND 3-WAY SOLENOID DESIGN.	SEE 10L211
[Symbol]	HUNTER	HPS-160 FLOW SENSOR FOR USE WITH ACC CONTROLLER, 1-1/2" SCHEDULE 40 SENSOR BODY, 24 VAC, 2 AMP.	SEE 10L211
[Symbol]	HUNTER	ICV-101Q-1F 1" PLASTIC ELECTRIC REMOTE CONTROL VALVES, GLOBE CONFIGURATION, WITH NPT THREADED INLETOUTLET, FOR COMMERCIAL/MUNICIPAL USE. WITH FILTER SENTRY.	SEE 7L211
[Symbol]	MATCO-NORCA	759 BRASS SHUT OFF BALL VALVE, 1/2" TO 4". TWO PIECE BODY, BLOW-OUT PROOF STEM, CHROME PLATED SOLID BRASS BALL, THREADED, WITH PTFE SEATS. SAME SIZE AS MAINLINE PIPE.	SEE 4L211
[Symbol]	HUNTER	HQ 44-LRC 1" BRASS QUICK-COUPLING VALVE, WITH CORROSION-RESISTANT STAINLESS STEEL SPRING, LOCKING THERMOPLASTIC RUBBER COVER, AND 2-PIECE BODY.	SEE 8L211
[Symbol]	HUNTER	SHRUB ROTARY	

IRRIGATION CONTROLLER

SYMBOL	MANUF.	MODEL NO. / DESCRIPTION	DETAIL
[Symbol]	HUNTER	IC-600-M W/2) ICM-600 MODULES MODULAR CONTROLLER, 16 STATIONS, OUTDOOR MODEL, METAL CABINET, WITH 1 MODULE REQUIRED, COMMERCIAL USE.	SEE 11L211
[Symbol]	HUNTER	VSS-SEN WIRELESS SOLAR, RAIN FREEZE SENSOR WITH OUTDOOR INTERFACE, CONNECTS TO HUNTER X-CORE CONTROLLER, INSTALL AS NOTED, INCLUDES CUTTER MOUNT BRACKET. MODULE NOT INCLUDED.	SEE 12L211
[Symbol]	N/A	120 VOLT POWER SUPPLY PROVIDED BY ELECTRICIAN, FIELD VERIFY LOCATION.	


IRRIGATION PIPING

SYMBOL	MANUF.	DESCRIPTION
[Symbol]	AS APPROVED	PRESSURE MAINLINE SCH. 40 PVC IN PLANTER AREAS FOR SIZES 3/4" - 1-1/2", FOR 2" & LARGER USE CLASS 315 PVC. BURY MIN. 18" BELOW GRADE (SIZE AS NOTED ON PLAN).
[Symbol]	AS APPROVED	TYPE 'K' COPPER PIPING MAINLINE DESIGNED BY PLUMBING ENGINEER AND SUPPLIED BY AND INSTALLED BY PLUMBER.



POTABLE WATER POINT OF CONNECTION
CONNECT IRRIGATION SYSTEM TO NEW 2"
POTABLE WATER METER FOR IRRIGATION ON THE
PODIUM. IN GRADE PIPING FROM WATER METER
SHALL BE PVC AND TRANSITION TO COPPER
PIPING AT LOWER LEVEL PER PLUMBING PLANS.
DESIGN PRESSURE:
TOTAL IRRIGATION DEMAND:
STATIC WATER PRESSURE AVAILABLE:

RECYCLED WATER POINT OF CONNECTION
CONNECT IRRIGATION SYSTEM TO NEW 2"
RECYCLED WATER METER FOR IRRIGATION.
METER SHALL BE SERVICED FROM THE WEST
BASIN MUNICIPAL WATER DISTRICT'S RECLAIMED
WATER SYSTEM. REFER TO RECYCLED WATER
STREET IMPROVEMENT PLANS FOR ADDITIONAL
INFORMATION.
DESIGN PRESSURE:
TOTAL IRRIGATION DEMAND:
STATIC WATER PRESSURE AVAILABLE:



1 LANDSCAPE IRRIGATION PLAN LEVEL 1
SCALE: 1/16" = 1'-0"

**HOLLYWOOD PARK
RESIDENTIAL - MU-2C**
INGLEWOOD, CALIFORNIA
HOLLYWOOD PARK RETAIL AND COMMERCIAL INVESTORS, LLC

**LANDSCAPE IRRIGATION PLAN
LEVEL 1 ENLARGEMENT**
NOT FOR CONSTRUCTION

THIS SET OF CONSTRUCTION
DOCUMENTS HAS BEEN
PREPARED FOR THE
CONSTRUCTION OF AN
APARTMENT PROJECT.

L12.04
2017-083
JOB NUMBER
DATE
PLOT PLAN
RESUBMITTAL
ISSUED AS
06-21-2018
DATE DATE