

IRRIGATION LATERAL LINE TO BE ROUTED THROUGH BUILDING ONTO ROOF TOP AREA AT THIS POINT. SHUT OFF VALVE TO BE INSTALLED AT P.O.C. FOR EASY MAINTENANCE. POINT SOURCE EMITTERS TO BE ADDED TO EACH POT

P.O.C.

SUBSURFACE IRRIGATION

SYMBOL	MANUF.	MODEL NO. / DESCRIPTION	DETAIL
[Symbol]	HUNTER	IC2-101-40-4F DRIP CONTROL ZONE KIT. 1" ICV GLOBE VALVE WITH 1" 1/4" X100 FILTER SYSTEM PRESSURE REGULATION: 40PSI. FLOW RANGE: 5 GPM TO 15 GPM. 150 MESH STAINLESS STEEL SCREEN.	SEE 1A1204
[Symbol]	HUNTER	DRIP LINE 0.4 GPH @ 12" O.C.	

IRRIGATION UTILITIES



SYMBOL	MANUF.	MODEL NO. / DESCRIPTION	DETAIL
[M]	WATER METER	1" DEDICATED LANDSCAPE METER, SEE CIVIL ENGINEER DWGS.	
[BS]	WYATT	BASKET STRAINER	
[M]	BUCKNER-SUPERIOR	3000 1-1/4" NORMALLY CLOSED BRASS MASTER VALVE THAT PROVIDES DIRTY WATER PROTECTION AND 3-WAY SOLENOID DESIGN.	SEE 10L1211
[FS]	HUNTER	HFS-150 FLOW SENSOR FOR USE WITH ACC CONTROLLER, 1-1/2" SCHEDULE 40 SENSOR BODY, 24 VAC, 2 AMP.	SEE 10L1211
[Symbol]	HUNTER	ICV-101G-FS 1" PLASTIC ELECTRIC REMOTE CONTROL VALVES. GLOBE CONFIGURATION WITH NPT THREADED INLET/OUTLET. FOR COMMERCIAL/MUNICIPAL USE. WITH FILTER ENTRY.	SEE 7A1211
[Symbol]	MATCO-NORCA	759 BRASS SHUT OFF BALL VALVE, 1/2" TO 4". TWO PIECE BODY, BLOW-OUT PROOF STEM, CHROME PLATED SOLID BRASS BALL, THREADED, WITH PTFE SEALS. SAME SIZE AS MAINLINE PIPE.	SEE 4L1211
[Symbol]	HUNTER	HQ 44-LRC 1" BRASS QUICK-COUPLING VALVE, WITH CORROSION-RESISTANT STAINLESS STEEL SPRING, LOCKING THERMOPLASTIC RUBBER COVER, AND 2-PIECE BODY.	SEE 8L1211
[Symbol]	HUNTER	SHRUB ROTARY	

IRRIGATION CONTROLLER

SYMBOL	MANUF.	MODEL NO. / DESCRIPTION	DETAIL
[C]	HUNTER	IC-600-AN W/12) ICM-800 MODULES MODULAR CONTROLLER, 18 STATIONS, OUTDOOR MODEL, METAL CABINET. WITH 1 MODULE REQUIRED. COMMERCIAL USE.	SEE 11L1211
[SS]	HUNTER	WSS-5EN WIRELESS SOLAR, RAIN FREEZE SENSOR WITH OUTDOOR INTERFACE. CONNECTS TO HUNTER XCCORE CONTROLLER. INSTALL AS NOTED. INCLUDES GUTTER MOUNT BRACKET. MODULE NOT INCLUDED.	SEE 12L1211
[E]	N/A	120 VOLT POWER SUPPLY PROVIDED BY ELECTRICIAN, FIELD VERIFY LOCATION.	

IRRIGATION PIPING

SYMBOL	MANUF.	DESCRIPTION
[Symbol]	AS APPROVED	PRESSURE MAINLINE SCH. 40 PVC IN PLANTER AREAS FOR SIZES 3/4" - 1-1/2", FOR 2" & LARGER USE CLASS 315 PVC. BURY MIN. 18" BELOW GRADE(SIZE AS NOTED ON PLAN).
[Symbol]	AS APPROVED	TYPE 'K' COPPER PIPING MAINLINE DESIGNED BY PLUMBING ENGINEER AND SUPPLIED BY AND INSTALLED BY PLUMBER.



**HOLLYWOOD PARK
RESIDENTIAL - MU-2C**
INGLEWOOD, CALIFORNIA
HOLLYWOOD PARK RETAIL AND COMMERCIAL INVESTORS, LLC

**LANDSCAPE IRRIGATION PLAN
LEVEL 3**
NOT FOR CONSTRUCTION

