

INGLEWOOD BASKETBALL & ENTERTAINMENT CENTER PROJECT

PRELIMINARY EARTHWORK QUANTITIES TABLE

	CUT	FILL
RAW (CY)	377,000	29,000
OVEREXCAVATION (CY)	156,000	156,000
SHRINKAGE (ASSUMED 3%)		6,000
EXPORT (CY)	342,000	
BULKING (ASSUMED 10%)	34,000	
NET EXPORT (CY)	376,000	

NOTE ALL EARTHWORK QUANTITIES ARE PRELIMINARY AND FOR ESTIMATE PURPOSES ONLY. QUANTITIES ARE BASED ON THE CONCEPTUAL GRADING PLAN AND INFORMATION AVAILABLE AT THE DATE OF THESE PLANS. THESE VALUES WILL BE ADJUSTED AS THE DESIGN PROGRESSES.

PRELIMINARY QUANTITIES ABOVE DO NOT ACCOUNT FOR FOOTINGS. ASSUMED SHRINKAGE AND BULKING ARE PER GEOTECHNICAL REPORT RECOMMENDATIONS. .

Source: D & D Engineering