

DAYTIME CONSTRUCTION	
LIGHT ACTIVITY AREA	
DAYTIME (7 AM - 8 PM)	
Install Sound Wall	
Tractors/Loaders/Backhoes	1
Demolition	
Concrete/Industrial Saws	1
Excavators	1
Rubber-Tired Dozers	1
Site Preparation	
Rubber-Tired Dozers	1
Drainage/Utilities/Trenching	
Concrete/Industrial Saws	1
Trenchers	1
Grading/Excavation	
Rubber-Tired Dozers	1
Tractors/Loaders/Backhoes	1
Paving	
Pavers	2
Paving Equipment	2
Rollers	2

DAYTIME CONSTRUCTION	
ACTIVITY AREA	
DAYTIME (7 AM - 8 PM)	
Install Sound Wall	
Cranes	1
Demolition	
Generator Set ^A	1
Concrete/Industrial Saws (Well)	1
Tractors/Loaders/Backhoes (Well)	1
Site Preparation	
Rubber-Tired Dozers	1
Tractors/Loaders/Backhoes	1
Drainage/Utilities/Trenching	
Concrete/Industrial Saws	1
Cranes	1
Generator Set ^A	1
Tractors/Loaders/Backhoes	1
Trenchers	1
Grading/Excavation	
Graders	1
Rubber-Tired Dozers	1
Scrapers	1
Tractors/Loaders/Backhoes	1
Foundations/Concrete Pour	
Tractors/Loaders/Backhoes	1
Concrete Pump	1
Building Construction	
Tractors/Loaders/Backhoes	1
Welders	5
Material Hoists	1
Concrete Pump	1
Aerial Lifts	5
Architectural Coatings	4
Generator Set ^A	2
Air Compressors	2

DAYTIME (7 AM - 8 PM)		EXTENDED HOURS (8 PM - 7 AM)	
Gradi	ing/	Excavation	
Excavators	2		
Drill Rig (Support of Excavation)	1		
Tieback Rig (Support of Excavation)	1		
Cranes	1		
Foundation	ons/	Concrete Pour	
Cranes	1	Drill Rig ^{B, C}	1
Drill Rig (Deep Foundations)	1	Concrete Pump ^{B, C}	1
Concrete Pump	1		
Generator Set ^A	1		
Buildin	ng C	onstruction	
Cranes	2	Cranes ^{C, D}	2
Welders	5	Welders	5
Material Hoists	1	Material Hoists	1
Concrete Pump	1	Concrete Pump ^{B, C}	1
Aerial Lifts	5	Aerial Lifts	5
Generator Set ^A	1		
Archite	ectu	ral Coatings	
Air Compressors	1		
Notes:			

Material devilvery and heavy equipment access from ramp to Century Blvd.

A Generator sets not required/operated after pole power fully avialable,

^c Equipment operation during extended hours anticipated to occur primarily below

anticipated 15 months after start of construction activities.

^D Crane engines at idle for extended construction hours.

^B Limited extended hours - 5:00 AM to 8:00 PM.

grade.

EXTENDED HOURS CO	ONST	RUCTION ACTIVITY AREA	
DAYTIME (7 AM - 8 PM)	DAYTIME (7 AM - 8 PM)		
Grad	ing/E	xcavation	
Drill Rig (Support of Excavation)	1		
Tieback Rig (Support of Excavation)	1		
Cranes	1		
Foundati	ons/	Concrete Pour	
Cranes	1	Cranes	1
Drill Rig (Deep Foundations)	1	Drill Rig ^{B, C}	1
Concrete Pump	1	Concrete Pump B, C	1
Buildi	ng Co	onstruction	
Cranes	4	Cranes ^{C, D}	4
Welders	5	Welders	10
Material Hoists	1	Material Hoists	1
Generator Set ^A	1	Generator Set ^A	1
Aerial Lifts	10	Aerial Lifts	10
Notes			

Anticipated extended hours activity required to secure pre-cast arena bowl elements and steel strucutral elements placed by cranes during daytime construction hours.

Anticipated extended hours activity may include limited use of concrete pump for pour at grade.

- A Generator sets not required/operated after pole power fully avialable, anticipated 15 months after start of construction activities.
- ^B Limited extended hours 5:00 AM to 8:00 PM.
- ^C Equipment operation during extended hours anticipated to occur primarily below grade.
- D Crane engines at idle for extended construction hours.

DAYTIME (7 AM - 8 PM)		EXTENDED HOURS (8 PM - 7 AM)	
Ī	nstall Sc	ound Wall	
Cranes			
Tractors/Loaders/Backhoes			
	Site Pre	paration	
Rubber Tired Dozers	1		
Dril	l/Install	New Casing	
Bore/Drill Rig	1	Bore/Drill Rig ^E	1
Air Compressors	1	Air Compressors ^E	1
Temporary Pump	1	Temporary Pump ^f	1
Forklifts	1		
Tractors/Loaders/Backhoes	1		
Eq	uip Wel	l & Utilities	
Generator Sets	1		
Bore/Drill Rigs	1		
Tractors/Loaders/Backhoes	1		
(Grade, Pa	ive, Fence	
Rollers	1		
Pavers	1		
Tractors/Loaders/Backhoes	1		
Notes			

Extended hours activity anticipated for 1 week.

installation.

^F Extended hours activity anticipated for 2 weeks (not concurrent with drill rig).